

Urbiztondo, Pangasinan, Philippines

BACK-UP COMPUTATION

B.3 (1) - Permits and Clearances									
Original Qty	=	1.00	L.S.						
V.O. # 1 Qty	=	1.00	L.S.						
B.5 (1) - Project Billboard/ Sign Board									
Original Qty	=	1.00	each						
V.O. # 1 Qty	=	2.00	each						
B.7(1) - Occupational Safety and Health									
Original Qty	=	1.00	L.S.						
V.O. # 1 Qty	=	1.00	L.S.						
B.8(1) - Traffic Management									
Original Qty	=	5.00	mo.						
V.O. # 1 Qty	=	5.00	mo.						
B.9 (1) - Mobilization / Demobilization									
Original Qty	=	1.00	L.S.						
V.O. # 1 Qty	=	1.00	L.S.						
B.24 (1) - General scaffolding and shoring and Netting									
Original Qty	=	1.00	L.S.						
V.O. # 1 Qty	=	1.00	L.S.						
803(1)a - Structure Excavation (Common Soil)									
Original Qty	=	113.32	cu.m.						
V.O. # 1 Qty	=	113.32	cu.m.						
F-1	=	1.90	x	1.90	x	1.30	x	16.00	= 75.09 cu.m.
FTB 1 (longitudinal)	=	0.40	x	0.85	x	12.90	x	4.00	= 17.54 cu.m.
FTB 1 (transverse)	=	0.40	x	0.85	x	12.90	x	4.00	= 17.54 cu.m.
WF	=	0.50	x	0.70	x	9.00	x	1.00	= 3.15 cu.m.
									<u>113.32 cu.m.</u>
804(2)a - Embankment from Borrow (Common Soil)									
Original Qty	=	52.27	cu.m.						
V.O. # 1 Qty	=	52.27	cu.m.						
SLAB ON FILL	=	13.20	x	13.20	x	0.30	x	1.00	= 52.27 cu.m.
									<u>52.27 cu.m.</u>
804(1)a - Embankment from Roadway/Structure Excavation (Common Soil)									
Original Qty	=	71.83	-						
V.O. # 1 Qty	=	71.83	cu.m.						
F-1	=	1.90	x	1.90	x	0.95	x	16.00	= 54.87 cu.m.
FTB 1 (longitudinal)	=	0.40	x	0.35	x	12.90	x	4.00	= 7.22 cu.m.
FTB 1 (transverse)	=	0.40	x	0.35	x	12.90	x	4.00	= 7.22 cu.m.
WF	=	0.40	x	0.70	x	9.00	x	1.00	= 2.52 cu.m.
									<u>71.83 cu.m.</u>
804(7) - Gravelfill									
Original Qty	=	26.06	cu.m.						
V.O. # 1 Qty	=	26.06	cu.m.						
F-1	=	1.80	x	1.80	x	0.10	x	16.00	= 5.18 cu.m.
FTB 1 (longitudinal)	=	0.30	x	12.90	x	0.10	x	4.00	= 1.55 cu.m.
FTB 1 (transverse)	=	0.30	x	12.90	x	0.10	x	4.00	= 1.55 cu.m.
WF	=	0.40	x	9.00	x	0.10	x	1.00	= 0.36 cu.m.
Slab	=	13.20	x	13.20	x	0.10	x	1.00	= 17.42 cu.m.
									<u>26.06 cu.m.</u>
900(1)a - Structural Concrete (Class A, 3000 psi @ 7 days)									
Original Qty	=	12.96	cu.m.						
V.O. # 1 Qty	=	26.68	cu.m.						
F-1	=	1.80	x	1.80	x	0.25	x	16.00	= 12.96 cu.m.
									<u>12.96 cu.m.</u>
R.C. Slab on Fill, Corridor & Ramp									
Qty	=	13.72	cu.m.						
1st flr. slab	=	13.20	x	13.20	x	0.10	x	1.00	= 17.42 cu.m.
	=	4.30	x	4.30	x	0.10	x	2.00	= 3.70 cu.m. (Deducted)
									<u>13.72 cu.m.</u>
900(1)b - Structural Concrete (Class A, 3000 psi @ 14 days)									
Original Qty	=	55.72	cu.m.						
V.O. # 1 Qty	=	54.20	cu.m.						

FTB 1 (longitudinal)	=	0.30	x	0.35	x	12.90	x	4.00	=	5.42	cu.m.
FTB 1 (transverse)	=	0.30	x	0.35	x	12.90	x	4.00	=	5.42	cu.m.
										10.84	cu.m.

Wall Footing:

WF-1	=	0.25	x	0.40	x	7.80	x	1.00	=	0.78	cu.m.
										0.78	cu.m.

2nd flr. slab	=	13.20	x	13.20	x	0.10	x	1.00	=	17.42	cu.m.
Area of Stair	=	0.03	x	1.20	x	15.00	x	1.00	=	0.50	cu.m.
	=	5.36	x	0.10	x	1.00	x	1.00	=	0.54	cu.m.
										18.46	cu.m.

R.C. for Columns

C-1	=	0.30	x	0.30	x	7.85	x	9.00	=	6.36	cu.m.
	=	0.30	x	0.30	x	5.59	x	7.00	=	3.52	cu.m.
										9.88	cu.m.

R.C. Roof Beams & LRB

RB-1	=	0.20	x	0.35	x	4.30	x	6.00	=	1.81	cu.m.
	=	0.20	x	0.35	x	4.30	x	6.00	=	1.81	cu.m.
										3.62	cu.m.

R.C. for Second Floor Beams & Lintel Beams

Qty	=	10.62	cu.m.								
B-1	=	0.25	x	0.40	x	4.30	x	12.00	=	5.16	cu.m.
	=	0.25	x	0.40	x	4.30	x	12.00	=	5.16	cu.m.
LB-1	=	0.20	x	0.35	x	4.30	x	1.00	=	0.30	cu.m.
										10.62	cu.m.

902(1)a1 - Reinforcing Steel (Deformed), Grade 40

Original Qty	=	10,081.70	kgs.
V.O. # 1 Qty	=	10,580.21	kgs.

Reinforcing Steel for Footing

Qty	=	1,155.34	kgs.								
no. of pcs	=	122	-	16.00	mm Ø x	6.00	m	=	1,155.34	kgs.	
										1,155.34	kgs.

Reinforcing Steel for Slab on Fill & Porch

Qty	=	181.26	kgs.								
no. of pcs	=	49	-	10.00	mm Ø x	6.00	m	=	181.26	kgs.	
										181.26	kgs.

Reinforcing Steel for Footing Tie Beam & Wall Footing

Qty	=	1,746.18	kgs.								
no. of pcs	=	118	-	16.00	mm Ø x	6.00	m	=	1,117.46	kgs.	
	=	157	-	10.00	mm Ø x	6.00	m	=	580.78	kgs.	
	=	9	-	12.00	mm Ø x	6.00	m	=	47.94	kgs.	
										1,746.18	kgs.

Reinforcing steel for Columns

Qty	=	2,542.25	kgs.								
no. of pcs	=	204	-	16.00	mm Ø x	6.00	m	=	1,931.88	kgs.	
	=	165	-	10.00	mm Ø x	6.00	m	=	610.37	kgs.	
										2,542.25	kgs.

Reinforcing Steel for Roofbeam

Qty	=	952.62	kgs.								
no. of pcs	=	67	-	16.00	mm Ø x	6.00	m	=	634.49	kgs.	
	=	86	-	10.00	mm Ø x	6.00	m	=	318.13	kgs.	
										952.62	kgs.

Reinforcing Steel for Second Floor Slab

Qty	=	1,635.79	kgs.								
no. of pcs	=	230	-	12.00	mm Ø x	6.00	m	=	1,225.18	kgs.	
	=	111	-	10.00	mm Ø x	6.00	m	=	410.61	kgs.	
										1,635.79	kgs.

Reinforcing Steel for Second Floor Beams

Qty	=	2,049.52	kgs.								
no. of pcs	=	134	-	16.00	mm Ø x	6.00	m	=	1,268.98	kgs.	
	=	211	-	10.00	mm Ø x	6.00	m	=	780.54	kgs.	
										2,049.52	kgs.

Reinforcing Steel for Stairs

Qty	=	317.25	kgs.								
no. of pcs	=	16	-	16.00	mm Ø x	6.00	m	=	151.52	kgs.	
	=	20	-	12.00	mm Ø x	6.00	m	=	106.54	kgs.	
	=	16	-	10.00	mm Ø x	6.00	m	=	59.19	kgs.	
										317.25	kgs.

1032(1)c - Painting Works (Steel)

Original Qty	=	4.32	m²
V.O. # 1 Qty	=	278.87	m²

108 = LC - 100 x 50 x 15 x 1.8mm x 6.0m
 7 = Steel Base Plates - 0.30m x 0.30m x 20mm Thick
 14 = Steel Base Plates - 0.30m x 0.30m x 10mm Thick
 6 = Angle Cleats - 2" x 2" x 3/16"
 2 = Pre-Fab. 8" dia. BI Post

1046(2)a1 - CHB Non-Load Bearing (including Reinforcing Steel), 100mm

Original Qty = 3.15 sq.m.
 V.O. # 1 Qty = 3.15 sq.m.

WF = 0.35 x 9.00 x 1.00 = 3.15 sq.m.
 3.15 sq.m.

1046(2)a2 - CHB Non-Load Bearing (including Reinforcing Steel), 150mm

Original Qty = 26.40 sq.m.
 V.O. # 1 Qty = 26.40 sq.m.

Embankment wall = 52.80 x 0.50 x 1.00 = 26.40 sq.m.
 26.40 sq.m.

1047(7) - Structural Steel

Original Qty = 1.00 L.S.
 V.O. # 1 Qty = 1.00 L.S.

1047(5)d - Metal Structure Accessories (Steel Plates)

Original Qty = 226.08 kgs.
 V.O. # 1 Qty = 197.82 kgs.

14 pcs. - Steel Base Plates - 0.30m x 0.30m x 10mm Thick = 98.91 kgs.
 7 pcs. - Steel Base Plates - 0.30m x 0.30m x 20mm Thick = 98.91 kgs.
 197.82 kgs.

1100(10) - Conduit, Boxes, & Fittings (Conduit Works/Conduit Rough-in)

Original Qty = 1.00 L.S.
 V.O. # 1 Qty = 1.00 L.S.

1001(8) - Sewer Line Works

Original Qty = 1.00 L.S.
 V.O. # 1 Qty = 1.00 L.S.

1001(9) - Storm Drainage and Downspout

Original Qty = 1.00 L.S.
 V.O. # 1 Qty = 1.00 L.S.

1002(24) - Cold Water Lines

Original Qty = 1.00 L.S.
 V.O. # 1 Qty = - L.S.

1047(8)b - Structure Steel (Purlins)

Original Qty = - kgs.
 V.O. # 1 Qty = 2,240.45 kgs.

108 pcs. - LC - 100 x 50 x 15 x 1.8mm x 6.0m = 2,105.94 kgs.
 6 pcs. - Angle Cleats - 2" x 2" x 3/16" = 134.52 kgs.
 2,240.45 kgs.

Prepared By:

Check By:

Noted By:
